Validate Print Help

Percentage BoQ

Tender Inviting Authority: Shri S.K. Gupta

Name of Work: Setting up of Exhibitions for IILF Kolkata & Tex styles-Kolkata 2017 (Feb. 26-28, 2017) at Milan Mela Ground, Kolkata during 2016-17. **Sub-Head :- Construction of stalls with pre-fab system, providing carpets, furniture items i/c electrical services like air conditioning, spot lights, power connections, audio visual arrangement etc. (on hire basis)**

Contract No:

Bidder Name :	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Construction of booth with bright finished/powder coated pre-fab aluminum O.C. system at site of work and putting up of lamination panels and facia of approved colour and shade which will be decided at the time of fair i/c facia writing with poly vinyl superior quality cut out letter of 3" height i/c providing office cabin where ever required i/c attending addition/alteration and maintenance during the fair period and dismantling the same after close of the fair as per the direction of Engineer-in-charge complete. (on hire basis for duration of fair)	1200.00	sqm	232.58	**279096**	INR Two Lakh Seventy Nine Thousand &Ninety Six Only
2	Providing built up podium 1mx1m with pre-fab OC system of various size / height. as per direction of Engg-in charge	2.00	each	239.78	**480**	INR Four Hundred & Eighty Only
3	Providing and laying on hire basis non-woven needle punch carpet of genuine fibre minimum over all weight 1000 gm/Sqm (+5%) having minimum 3.90 mm thickness preferable containing 375 gm polyester fibre or equivalent fibre (+5%) and the carpet should not loss the thickness more then 25 % after 1000 impact and of required shade and laying with approved adhesive or double side tape wherever required etc as per direction of Engg-in-charge i/c covering with polythene sheet till the inauguration of fair a)Using brand new carpet	3000.00	sqm	71.93	**215790**	INR Two Lakh Fifteen Thousand Seven Hundred & Ninety Only
4	Providing table cum counter made up of octonorm system with laminated top of size 1.00x0.50x0.75m i/c cartage loading and unloading as per the approved shade/sample and direction of Engg.-in-charge. (On hire basis for duration of fair)	140.00	Each	179.83	**25176**	INR Twenty Five Thousand One Hundred & Seventy Six Only
5	Providing good quality exhibition chair folding type with canvas top or fixed arms seat and back i/c cartage loading and unloading as per the approved shade/sample and direction of Engg.-in-charge. (On hire basis for duration of fair).	20.00	each	35.97	**719**	INR Seven Hundred & Nineteen Only
6	Providing good quality executive chair in attractive colours with nickel polished/powder coated frame & cushion seat & back as per the direction of Engg.-in-charge. (On hire basis for duration of fair).	400.00	each	179.84	**71936**	INR Seventy One Thousand Nine Hundred & Thirty Six Only
7	P/F digitally printed name boards of required sizes indicating the names of participants at the gate etc. and as per the direction of Engineer-in-charge.	300.00	sqft	35.97	**10791**	INR Ten Thousand Seven Hundred & Ninety One Only
8	Providing/ Fixing wooden name boards, signage/buntings of soft wood frame/M.S frame of required section & of required size covered with Flex sheet of desired shade & text as approved by Engineer in charge indicating the name of Fair as International Leather Goods Fair 2015, Kolkata (March 27 to 29, 2015) or See you at ILGF, 2016 etc. for all heights etc. complete as per the direction of Engg. In charge. (On hire basis only).	2500.00	sqft	35.97	**89925**	INR Eighty Nine Thousand Nine Hundred & Twenty Five Only

9	Providing Shelves connected to OC system with anodized/powder coated bracket matching with existing octonorm system of size 1.00 m x 0.30 m and as per direction of Engg.-in-charge. (on hire basis for duration of fair). (a) 5.5 mm thick glass panes	350.00	each	179.83	**62941**	INR Sixty Two Thousand Nine Hundred & Forty One Only
10	Supply of 1 ft. x 1ft wooden painted name plate self standing stands with name like press, VIP, delegates etc. with white painted and letter in orange colours (on hire basis).	15.00	each	59.94	**899**	INR Eight Hundred & Ninety Nine Only
11	Providing waste paper basket in stall for fair period on hire basis (on hire basis).	130.00	each	9.59	**1247**	INR One Thousand Two Hundred & Forty Seven Only
12	Hire charges for erecting flag poles duly painted after making required holes in grounds making good the holes putting up flags etc. complete.	50.00	each	119.89	**5995**	INR Five Thousand Nine Hundred & Ninety Five Only
13	Supplying Sofa sets (Three, two, single seater) in pretty good condition for inauguration etc. at site complete (on Hire basis) i/c loading, unloading, Carriage.	30.00	each set	359.67	**10790**	INR Ten Thousand Seven Hundred & Ninety Only
14	Printing of signage of height 1m and length as per size of the gate to be fixed to MS Frame work and placed at gate on different location in the ground erected as an independent structure made of combination of Quardro girder and M 12 space frame or Metallic structure. The structure will have an overall height of 5.00 mtr Height and clear height of 4 mtr. And the printed signage will be fixed on both sides of the gate/all around vertical pillars etc on flex as per drawing and the direction of Engineer-in-Charge (on hire basis).	10.00	RM	8392.23	**83922**	INR Eighty Three Thousand Nine Hundred & Twenty Two Only
15	Arrangement of cleaning & upkeep of stalls & passage i/c outside adjoining exhibition area, attached toilets, i/c providing cleaning material for toilets, collecting garbage in garbage bins for fair period i/c sprinkling water etc. where ever required-Complete	1.00	each job	14532.00	**14532**	INR Fourteen Thousand Five Hundred & Thirty Two Only
16	Arrangement of cleaning & upkeep of food Court i/c outside adjoining area, attached toilets, i/c providing cleaning material	1.00	each job	9591.12	**9591**	INR Nine Thousand Five Hundred & Ninety One Only
17	Providing Registration counter made with superior quality O.C. system including facia write up and counter of size (length as per front opening of booth x 0.50 m width x 0.75 m height) i/c scratch less laminated top with projected shelf in front of counter etc as per drawing and the direction of Engineer-in-Charge. (The item includes, octonorm system, counters, front shelf and facia write up etc complete) (A) As per drawing attached with roof i/c covering roof with G I sheet/Profile sheets/Canopy structure with water proof Fabric including providing wooden platform.	21.00	sqm	779.28	**16365**	INR Sixteen Thousand Three Hundred & Sixty Five Only
18	Supply on hire basis healthy plant material in neat and clean flower pots of the following type of plants: a) Flowering bougainvilleas size 3 to 4 ft ht. in pots	150.00	each	35.97	**5396**	INR Five Thousand Three Hundred & Ninety Six Only
18.1	b) Decorative colours foliage plants of size 3 to 4 ft ht. in pots	150.00	each	35.97	**5396**	INR Five Thousand Three Hundred & Ninety Six Only
18.2	c) Monasteries in drums of size2 to 3 ft.	150.00	each	35.97	**5396**	INR Five Thousand Three Hundred & Ninety Six Only
18.3	d) Evergreen small plants like chocophtum asparagus, ferns, treedescancies etc. In pots.	250.00	each	33.57	**8393**	INR Eight Thousand Three Hundred & Ninety Three Only
18.4	e) Floral annual of 2 to 3 ft ht such as chrysabanthynoon marigold Delhi as etc.	250.00	each	35.97	**8993**	INR Eight Thousand Nine Hundred & Ninety Three Only
19	Floral decoration of main entrance gates to exhibition ground, entrance/exit gates of halls & side walls etc. i/c for lighting of lamps etc complete at Milan Mela Ground.	1.00	each job	5994.45	**5994**	INR Five Thousand Nine Hundred & Ninety Four Only
20	Information/form filling counter made with superior quality O.C. system including a set of 5 Nos PVC jacket for keeping the forms and the size of the counter will be 1.00m x 0.50 m x 0.75 m with scratch less laminated top as per the direction of Engineer-in-Charge. (The item includes PVC Jackets ,octonorm system wall and counter etc complete) 1 m long	2.00	each	435.96	**872**	INR Eight Hundred & Seventy Two Only
21	Covering/ enclosing areas with OC wall having laminated ply panels as per the direction of Engineer in charge. (A) 2.50 mtr height	150.00	meter	391.94	**58791**	INR Fifty Eight Thousand Seven Hundred & Ninety One Only

21.1	(B) 5.00 to 6.00 mtr height	25.00	meter	742.50	**18563**	INR Eighteen Thousand Five Hundred & Sixty Three Only
22	Covering/ enclosing areas with OC wall having textile panels and as per the direction of Engineer in charge. A) 2.50 mtr height. (Textile panels to be supplied by the department)	50.00	meter	195.96	**9798**	INR Nine Thousand Seven Hundred & Ninety Eight Only
23	Good quality steel almirah as per the direction of Engineer in charge. a) Medium size…0.90 x 0.40 x 1.50m	2.00	each	1808.96	**3618**	INR Three Thousand Six Hundred & Eighteen Only
24	Construction of inauguration stage of size 25 feet x 15 feet & about 2 feet 6" to 3 feet 6" height using casuarinas or available balli frame 2feet c/c vertically, horizontally and also diagonally with 20 mm thick commercial boards on top covered with new synthetic carpet of good quality, and of required shade with back drop of size25 feet x 8 feet i/c write up work for fair & providing two Wings of 3 feet x 8 feet. All the visible sides will be finished with plastic emulsion paint of required shade and shall be decorated Nicely i/c steps of both sides including 100 numbers of chairs for inauguration as well as during fair period and as per the direction of Engg-in Charge. (on hire basis).	375.00	sqft	85.60	**32100**	INR Thirty Two Thousand One Hundred Only
25	Providing Centre Table in rectangular shape of size 0.90x0.45m for different purpose as per the direction of Engineer-in-charge(on hire basis for duration of fair).	5.00	each	482.39	**2412**	INR Two Thousand Four Hundred & Twelve Only
26	Extra for providing lockable door spotless/scratch less superior quality of required size for the office cabins with matching shade of system as per the direction of Engg.-in-charge (on hire basis for duration of fair).	2.00	each	1034.58	**2069**	INR Two Thousand &Sixty Nine Only
27	Providing Podium/Rostrum of required size and shape for event of opening/closing ceremony as per the direction of Engineer-in-charge. (For 3 days)	1.00	each	2400.00	**2400**	INR Two Thousand Four Hundred Only
28	Supply of tables of size 1.50x0.75x0.75m with frills and covers for upto 3 days for event including loading, unloading and placing in position etc. as per the direction of Engineer in charge.	3.00	each	98.09	**294**	INR Two Hundred & Ninety Four Only
29	Hire charges for providing air-conditioning facility in various hangers at different locations in Pragati Maidan complex during the event **by using air cooled package/ split air-conditioning units of suitable capacity as required** alongwith connecting refrigent piping from outdoor to indoor units, gas charging, internal/electrical connections complete with installations testing and commisioning of the units in all respects and maintenance of the equipments during the event.	600.00	sqm	320.00	**192000**	INR One Lakh Ninety Two Thousand Only
30	Providing and fixing main distribution angle iron Board with 200/300Amps. TPN AC main switch fuse unit including connecting up and providing double loop earthing with the main CPWD/WBEB Existing power outlet, on hire basis for fair period as reqd.	4.00	each	4904.55	**19618**	INR Nineteen Thousand Six Hundred & Eighteen Only
31	P/F main distribution angle board with 100/60 Amps. TPN 440V. AC main switch fuse unit bus bar chamber of suitable capacity i/c connecting up & providing double loop earthlings etc.on hire basis for period as reqd. (For lighting / power circuits)	8.00	each	3487.68	**27901**	INR Twenty Seven Thousand Nine Hundred & One Only
32	Providing and laying of following sizes of 3 ½ core PVC insulated and PVC sheathed Al. conductor armoured cable including connections and interconnections, double loop earthing wire etc. as required (on hire charges for the fair period) 3 ½ core 120sq.mm. to 240sq.mm.	120.00	RM	217.98	**26158**	INR Twenty Six Thousand One Hundred & Fifty Eight Only
33	P/Laying main of 3 ½ core armoured L T cable of 1100 Volts grade 16 sq. mm to 70 sq. mm size on ground / overhead i/c connections, interconnections & earthing etc. as reqd on hire basis for the fair period.	600.00	meter	30.52	**18312**	INR Eighteen Thousand Three Hundred & Twelve Only
34	Providing & fixing 5/15 amps universal type switch socket, combination box complete with wiring connections/ interconnections and earthing the third pin as required on hire basis for fair period (no separate payment against power load item will be made)	160.00	each	217.98	**34877**	INR Thirty Four Thousand Eight Hundred & Seventy Seven Only
35	Hire charges for supplying, installation, testing and commissioning of Arm type spot light fittings (powder coated aluminum/ black finish) with 6 to 20 Watt LED lamp (pin/screw type) suitable for mounting on cyma/Octonorm system with rail and plug type accessories complete with connections, interconnections, sub main circuit, control wiring and switchgear etc. i/c their maintenance during the fair period etc. as required.	200.00	each	159.13	**31826**	INR Thirty One Thousand Eight Hundred & Twenty Six Only

36	Hire charges for supplying, installation, commissioning and testing of 100W Arm type spot light fittings (powder coated aluminum/ black finish) with 23 Watt CFL/ 100 Watt comptalux lamp (pin/screw type) suitable for mounting on cyma/Octonorm system with rail and plug type accessories complete with connections, interconnections, sub main circuit, control wiring and switchgear etc. i/c their maintenance during the fair period etc. as required.	650.00	each	99.18	**64467**	INR Sixty Four Thousand Four Hundred & Sixty Seven Only
37	Providing and installation of 1000 Watt Halogen light fittings on existing pole/trees/walls complete with 1000Watt Halogen lamp, heat resistance glasses connections etc. as required(on hire basis for fair period)	10.00	each	1089.90	**10899**	INR Ten Thousand Eight Hundred & Ninety Nine Only
38	Providing and fixing of flood lights 250/400Watt Mercury lamp/Metal halide light fittings complete with connections on hire basis for fair period as required.	10.00	each	1089.90	**10899**	INR Ten Thousand Eight Hundred & Ninety Nine Only
39	Providing and fixing the16"/24" pedestal fans including transportation & maintenance during the fair period .	15.00	each	741.13	**11117**	INR Eleven Thousand One Hundred & Seventeen Only
40	Providing PA system with suitable nos. of box type speaker, playing of music system/cassette player and microphone (including inauguration) for announcement complete with service in the halls and office of ITPO with change over type microphone etc for the fair period etc. as required.	1.00	Ezch Job for 4 days	13078.80	**13079**	INR Thirteen Thousand &Seventy Nine Only
41	Hire charges for providing power connections with suitable size of aluminium/copper conductor cables along with earthing from electric substations / D.B. to power switch board for Machines and connected with suitable size of switchgear during the fair period.	50.00	KW	212.53	**10627**	INR Ten Thousand Six Hundred & Twenty Seven Only
42	Hiring & fixing of 60-80 Watt LED light fitting on parapet wall/pole and making connection with suitable size of aluminium/copper conductor cable/wire, complete with connections, interconnections, sub main wiring etc. on hire basis for fair period as required.	20.00	each	640.00	**12800**	INR Twelve Thousand Eight Hundred Only
43	Supplying and filing of Diesel oil in existing D.G Sets installed at Milan Mela Ground complete with transportation loading and unloading etc. as required during the fair period.	500.00	litre	73.00	**36500**	INR Thirty Six Thousand Five Hundred Only
44	Note: Tax will be charge extra as applicable.					
Total in Figures					**1591760**	INR Fifteen Lakh Ninety One Thousand Seven Hundred & Sixty Only
Quoted Rate in Figures			**Select**		**0.00**	INR Zero Only
Quoted Rate in Words					**INR Zero Only**	