Validate Print Help

Item Rate BoQ

Tender Inviting Authority: ITPO Pragati Maidan New Delhi

Name of Work: Providing Power load during various events organized by ITPO on hire charges basis at Pragati Maidan New Delhi.

Contract No: 167-ITPO(1)E-E/2019-20/1771

Name of the Bidder/ Bidding Firm /	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	**Item Description**	**Quantity**	**Units**	**BASIC RATE With all Taxes including GST In Figures To be entered by the Bidder in Rs. P**	**TOTAL AMOUNT With Taxes including GST in Rs. P**	**TOTAL AMOUNT In Words**
1	**2**	**4**	**5**	**13**	**53**	**55**
1	Providing and fixing main distribution angle iron Board with 400/630Amps. TPN AC main switch fuse unit including connecting up and providing double loop earthing with the main power outlet on hire basis for fair period as reqd.	20.000	Each		**0.00**	INR Zero Only
2	Providing and fixing main distribution angle iron Board with 200/300Amps. TPN AC main switch fuse unit including connecting up and providing double loop earthing with the main power outlet on hire basis for fair period as reqd.	150.000	Each		**0.00**	INR Zero Only
3	Providing and fixing of main distribution angle iron board with 100/60Amps. TPN 440V. AC main switch fuse unit with bus bar chamber of suitable capacity including connection, double loop earthing etc. on hire basis for fair period as reqd.(for lighting/domestic power switches)	40.000	Each		**0.00**	INR Zero Only
4	Providing and laying/fixing of 3 ½ core armoured LT cable of 1.1 KV grade 300sq. mm. to 400 sq. mm. size ,PVC insulated and PVC sheathed, armoured aluminium conductor cables on ground/overhead including connections, interconnections and earthing by providing & laying two 6 SWG,GI /aluminum/copper wires with cable etc. as required (on hire basis for fair period)	3000.000	Mtr		**0.00**	INR Zero Only
5	Providing and laying/fixing of 3 ½ core armoured LT cable of 1.1 KV grade 120sq. mm. to 240 sq. mm. sizePVC insulated and PVC sheathed, armoured aluminium conductor cables on ground/overhead including connections, interconnections and earthing by providing & laying two 6 SWG,GI /aluminum/copper wires with cable etc. as required (on hire basis for fair period)	30000.000	Mtr		**0.00**	INR Zero Only
6	Supplying, laying and fixing of 1.1 KV grade ,16-70 sq.mm.size , PVC insulated and PVC sheathed, armoured aluminium conductor cables in ground / on over head poles including connections , interconnections and earthing by providing & laying two 6 SWG,GI /aluminum/copper wires with cable etc. as required on hire basis for fair period.	3000.000	Mtr		**0.00**	INR Zero Only
7	Providing, fixing testing & commissioning of 60-80 Watt LED light fitting on poles/wall complete with connection interconnection,wiring etc.as required for illumination in dark areas during the events organized in pragati maidan New Delhi.	300.000	Each		**0.00**	INR Zero Only
Total in Figures					**0.00**	INR Zero Only
Quoted Rate in Words		**INR Zero Only**				