AMENDED UPTO CON 265 CPWD ï 6

GOVERNMENT OF INDIA

INDIA TRADE PROMOTION ORGANISATION

NOTICE INVITING TENDER

Item rate/**percentage** rate tenders are invited on behalf of the CMD, ITPO from approved and eligible contractors of ITPO, CPWD and those of appropriate list of Department of Telecommunications, M.E.S., Railways **up to 3.00 PM on 09/10/2017,** which will be opened on the same day by him (or) his authorized representative at **3.30 PM** for the work of **Construction of new single unit toilet for security guards and Mali at ITPO's land at Ghazipur.**

The enlistment of the contractors should be valid on the last date of sale of tenders.

In case only the last date of sale of tender is extended, the enlistment of contractor should be valid on the original date of sale of tenders.

In case both the last date of receipt of application and sale of tenders are extended, the enlistment of contractor should be valid on either of the two dates i.e. original date of sale of tender or on the extended date of sale of tenders.

1.1 The work is estimated to cost **1, 35,644/-.** This estimate, however, is given merely as a rough guide.

1.1.1. The authority competent to approve NIT for the combined cost and belonging to the major disciple will consolidate NITs for calling the tenders. He will also nominate Division which will deal with all matters relating to the invitation of tenders.

For composite tender, besides indicating the combined estimated cost put to tender, should clearly indicate the estimated cost of each component separately. The eligibility of tenderer will correspond to the combined estimated cost of different components put to tender.

1.2 Tenders will be issued to eligible contractors provided they produce definite proof from the appropriate authority, which shall be to the satisfaction of the competent authority, of having satisfactorily completed similar works of magnitude specified below:-

1.2.1 Conditions for Non – CPWD contractors only, if tenders are also open to non-CPWD contractors.

For works estimated to cost up to Rs.15 Crore. – not applicable for this work.

Three similar works each of value not less than 40% of estimated cost or two similar work each of value not less than 60% of estimated cost or one similar work of value not less than 80% of estimated cost (rounded to nearest Rs.10 lac) in last 7 years ending last day of the month previous to the one in which the tenders are invited.

Note: For works costing above Rs. 3 crore but up to Rs. 15 crore, when tenders are open to non- CPWD contractors also, then class II contractors of CPWD shall also be eligible if they satisfy the eligibility criteria specified in 1.2.1 above.

1.2.2 Criteria of eligibility for CPWD as well as on- CPWD contractors.

For works estimated to cost above Rs. 15 crore. – not applicable for this work

Three similar works each of the value not less than 40% of estimated cost of two similar work each of value not less than 60% of estimated cost or one similar work of value not less than 80% of estimated cost (rounded to nearest Rs. 10 lac) in last 7 years ending last day of the month previous to the one in which the tenders are invited.

The value of executed works shall be brought to current costing level by enhancing the actual value of work at simple rate of 7% per annum, calculated from the date of completion to the last date of receipt of applications for tender

2. Agreement shall be drawn with the successful tenderer on prescribed Form No. C.P.W.D. 7/8 which is available as a Govt. of India publication. Tenderer shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.

3. The time allowed for carrying out the work will be **30 days** from the date of start as defined in schedule óFô or from the first date of handing over of the site, whichever is later, in accordance with the phasing, if any, indicated in the tender documents.

4. The site for the work is available.

OR

The site for the work shall be made available in parts as specified below:

5. Applications for issue of forms shall be received by Senior Manager (Civil) up to 3.00 PM and tender documents shall be issued by Senior Manager (Civil) up to 3.00 PM. Tender documents consisting of plans, specifications, the schedule of quantities of the various classes of work to be done and the set of terms & conditions of contract to be compiled with by the contractor whose tender may be accepted and other necessary documents can be seen in the office of the Senior Manager (Civil) between hours of 11.00 A.M. & 03.00 P.M. from **29/09/2017 to 06/10/2017** everyday except Saturday, Sundays and public Holidays. Tender documents excluding standard form, will be issued from his office, during the hours specified above, on payment of **Rs. 590/-** in cash as cost of tender.

6. (i) Tenders shall be accompanied with Earnest money of Rs**. 2720/-** in cash (up to Rs.10000) demand draft of a scheduled bank issued in favour of India Trade Promotion Organisation, New Delhi. 50% of earnest money or Rs.20 lakh, whichever is less, will have to be deposited in the shape prescribed above and balance amount of earnest money can be accepted in the form of Bank guarantee issued by a scheduled bank having validity for 6 months or more from the last date of receipt of tenders.

ii) The tender and the earnest money shall be placed in separate sealed envelopes, each marked ñTenderò and ñEarnest Moneyò respectively. In cases where earnest money in cash is acceptable, the same shall be deposited with the Cash section of ITPO and the receipt placed in the envelope meant for earnest money. Both the envelopes shall be submitted together in another sealed envelope with the name of work and due date of opening written on envelope, which will be received by the Senior Manager (Civil) up to 3.00 P.M. on **09/10/2017** and will be opened by him or his authorised representative in his office on the same day at 3.30 P.M. The envelope marked ñTenderò of only those tenderers shall be opened, whose earnest money, placed in the other envelope, is found to be in order.

7. The Contractor whose tender is accepted, will be required to furnish performance guarantee of 5% (Five percent) of the tendered amount within the period specified in Schedule F. This guarantee shall be in the form of cash (in case guarantee amount if less than Rs.10,000/-) OR Demand Draft of any scheduled bank/Pay order of any scheduled bank (in case guarantee amount is less than Rs.1,00,000/-) or Government Securities or Fixed Deposit Receipts or Guarantee Bonds of any Scheduled Bank or the State Bank of India in accordance with the prescribed from. In case the contractor fails to deposit the said performance guarantee within the period as indicated in Schedule óFô, including the extended period if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor.

8. The description of the work is as follows:

Copies of other drawings and documents pertaining to the works will be open for inspection by the tenderers at the office of the above mentioned officer.

Tenderers are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their tender. A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charges consequent on any misunderstanding or otherwise shall be allowed. The tenderer shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a tender by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and of conditions and rates at which stores, tools and plant, etc. will be issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.

9. The competent authority on behalf of the CMD, ITPO does not bind itself to accept the lowest or any other tender and reserves to itself the authority to reject any or all the tenders received without the assignment of any reason. All tenders in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.

10. Canvassing whether directly or indirectly, in connection with tenders if strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.

11. The competent authority on behalf of CMD, ITPO reserves to himself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the rate quoted.

12. No Engineer of gazetted rank or other Gazetted officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the previous permission of the Government of India in writing. This contract is liable

to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as aforesaid before submission of the tender or engagement in the contractorôs service.

13. The tender for the works shall remain open for acceptance for a period of ninety (90) days from the date of opening of tenders/Ninety days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system (strike out as the case may be) if any tenderer withdraws his tender before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the tender which are not acceptable to the department, then the Government shall, without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money as aforesaid. Further the tenderer shall not be allowed to participate in the re-tendering process of the work.

14. This Notice Inviting Tender shall form a part of the contract document. The successful tenderer/contractor, on acceptance of his tender by the Accepting Authority, shall, within 15 days from the stipulated date of start of the work, sign the contract consisting of:-

a) The notice inviting tender, all the documents including additional conditions, specification and drawings, if any, forming the tender as issued at the time of invitation of tender and acceptance thereof together with any correspondence leading thereto.

b) Standard C.P.W.D. Form **7**/8

S. K. Gupta
Senior Manager (Civil)

ITPO

CPWD-7/8

GOVERNMENT OF INDIA
CENTRAL PUBLIC WORKS DEPARTMENT

STATE: Delhi		CIRCLE	Civil
BRANCH: Engg.		DIVISION:	**Senior Manager (Civil)**
ZONE	Head office, Delhi	SUB DIVISION:	M (SK)

Percentage Rate Tender/Item Rate Tender & Contract for Works

Tender for the work of: **Construction of new single unit toilet for security guards and Mali at ITPO's land at Ghazipur.**

(i)To be submitted **3.00 p.m.** (Time) **Hours on** **09/10/2017** (Date)

(ii)To be opened in presence of tenderers, who may be present at 3.30 **p.m.** **Hours on** **09/10/2017** in the office of SM (S K Gupta) at Pragati Maidan, New Delhi

Issued to: _____
(Contractor)

Signature of officer issuing the documents
Designation: Senior Manager (Civil)

Date of issue: ` ----------
Estimated Cost **Rs** **1, 35,644/-**
Earnest Money **Rs.** **2720/-**

TENDER

I/We have read and examined the notice inviting tender, schedule, A, B, C, D, E & F, Specifications applicable, drawings & Designs, General Rules and Directions, Conditions of Contract, clauses of contract, special conditions, Schedule of Rate & other documents and Rules referred to in the conditions of contract and all other contents in the tender document for the work.

I/We hereby tender for the execution of the work specified for the President of India within the time specified in Schedule óFô, viz., schedule of quantities and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule ï 1 of General Rules and Directions and in Clause 11 of the Conditions of contract and with such materials as are provided for, by, and in respect in accordance with, such conditions so far as applicable.

We agree to keep the tender open for Ninty (90) days from the due date of its opening and not to make any modifications in its terms and conditions.

ITPO

A sum of **Rs 2720/-** has been deposited as per NIT as earnest money. If I/we, fail to furnish the prescribed performance guarantee within prescribed period, I/we agree that the said President of India or his successors in office shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/we fail to commence work as specified, I/we agree that President of India or his successors in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said earnest money and the performance guarantee absolutely, otherwise the said earnest money shall be retained by him towards security deposit to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to therein and to carry out such deviations as may be ordered, upto maximum of the percentage mentioned in Schedule óFô and those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.3 of the tender form. Further, I/We agree that in case of forfeiture of earnest money or both Earnest Money & Performance Guarantee as aforesaid, I/We shall be debarred for participation in the retendering process of the work.

I/We hereby declare that I/we shall treat the tender documents drawings and other records connected with the work as secret/confidential documents and shall no communicate information/derived there from to any person other than a person to whom I/we am/are authorised to communicate the same or use the information in any manner prejudicial to the safety of the State.

Datedé é é é é é é é é .. Signatures of Contractor

Postal Address

Witness:

Address:

Occupation:

ACCEPTANCE

The above tender (as modified by you as provided in the letters mentioned hereunder) is accepted by me for and on behalf of the President of India for a sum of Rsé é é é é é é é é é é ..(Rupeesé)

The letters referred to below shall form part of this contract Agreement:-

(1) Schedule of Quantities, NIT
(2) Additional Conditions.
(3) Wages for workers
(4) Performa for Agreement and drawing of staircase

For & on behalf of President of India

Signatureé é é é é é é ..

Datedé é é é é é é Designationé é é é é é é .

ITPO

SCHEDULES

SCHEDULE 'A'

Schedule of quantities Enclosed

SCHEDULE 'B'

Schedule of materials to be issued to the contractor.

S.No.	Description of item	Quantity	Rates in figures & words at which The material will be charged to the Contractor	Place of issue
2.	2	3	4	5

NIL

SCHEDULE 'C'

Tools and plants to be hired to the contractor

S.No.	Description	Hire charges per day	Place of issue
1.	2.	3	4

NIL

SCHEDULE 'D'

Extra schedule for specific requirements/documents for the work, if any.

ï N/A

SCHEDULE 'E'

Schedule of component of Cement, Steel, other materials, Labour etc. for price escalation.- Nil

CLAUSE 10 CC

Component of Cement ï expressed as percent of total value work.	N/A
Component of Steel-expressed as percent of total work.	N/A
Component of civil (except cement & steel)/Electrical construction Materials-expressed as percent of total value of work.	N/A
Component of labour-expressed as per cent of total value of work.	N/A
Component of P.O.L. ï expressed as percent of total value work.	N/A

SCHEDULE 'F'

Reference to General Conditions of contract.

Name of work: **Construction of new single unit toilet for security guards and Mali at ITPO's land at Ghazipur.**

i)	Estimated cost of work	Rs.	**1, 35,644/-**
ii)	Earnest money:	Rs.	**2720/-**
iii)	Performance Guarantee	5% of tendered value	
iv)	Security Deposit	5% of tendered value	

General Rules & Directions:

Officer inviting tender — Senior Manager (Civil)

Maximum percentage for quantity of items of work to be executed beyond Which rates are to be determined in accordance with Clauses 12.2 & 12.3 — 100%

Definitions

2(v)	Engineer-in-Charge	Senior Manager (Civil)
2(viii)	Accepting Authority	As per DFPR Sch. V of ITPO
2(x)	Percentage on cost of materials and Labour to cover all overheads and profits.	15%
2(xi)	Standard Schedule of Rates	DSR-2016 & market rates
2(xii)	Department	ITPO (Engg.)
9(ii)	Standard CPWD contract Form	CPWD form **7**/8 as modified & corrected upto date

Clause 1

(i) Time allowed for submission of Performance Guarantee From the date of issue of letter of acceptance — 7 days

(ii) Maximum allowable extension beyond the period (Provided in i) above — 4 days

Clause 2

Authority for fixing compensation under clause 2. — GM (W)

Clause 2A

Whether clause 2A shall applicable — No

Clause 5

Number of days from the date of issue of letter
Acceptance for reckoning date of start 4 days

ITPO

Mile stone(s) as per table given below:

Table of Mile Stone(s)

Sl. No.	Description of Milestone(Physical)	Time allowed in days (from date of start)	Amount to be withheld in case of non achievement of milestone
1.	1/8th (of the whole work)	1/4th (of the whole work)	In the event of not achieving the necessary progress as assessed from the running payments, 1% of the tendered value of work will be withheld for failure of each mile stone.
2.	3/8th (- do -)	½ (- do -)	
3.	3/4th (-do-)	3/4th (-do-)	
4.	Full	Full	

Time allowed for execution of work 30 **days**

Clause 6, 6A
Clause applicable ï (6 or 6A) Clause 6A
Clause 7
Gross work to be done together with net payment/adjustment N A
or advance for material collected, if any since the last such payment
for being eligible to interim payment
Clause 10A
List of testing equipment to be provided by the contractor at site lab.

As per the site requirement and as per direction of Engineer Incharge

Clause 10 B (ii)

Whether Clauses 10 B (ii) shall be applicable No

Clause 10CA

Materials covered under this clause Nearest Material for which All India Wholesale Price Index is to be Followed

1._____ _____NA_____

2._____ _____
3._____ _____

Clause 10CC
Clause 10CC to be applicable in contracts with stipulated period of
Completion exceeding the period show in text column 18 months

Clause 11
Specification to be followed for execution of work CPWD Specifications 2009, Part I & II with Up-to-date correction slips.

Clause 12
Deviation limit beyond which clauses 12.2 & 12.3 shall
Apply for building work 50%
Deviation limit beyond which clauses 12.2. & 12.3
Shall apply for foundation work 100%
Clause 16

Competent Authority for deciding reduced rates. GM (W)

Clause 18

List of mandatory machinery, tools & plants to be deployed by the contractor at site:-

As per the site requirement and as per direction of Engineer Incharge

Clause 36(i)

S.N.	Minimum qualification of Technical Representative	Discipline	Designation (Principal Technical/Technical representative)	Minimum experience	Number	Rate at which recovery shall be made from the contractor in the event of not fulfilling provision of clause 36(i)
						Figures Words
1. 2.	Graduate Engineer Or Diploma Holder	Civil	Principal Technical	Nil 5 years	1 1	15,000/- (Rupees fifteen thousand only) per month

Assistant Engineers retired from Government services that are holding Diploma will be treated at par with Graduate Engineers.

CLAUSE 42

(i)(a) Schedule/statement for determining theoretical quantity of cement & Bitumen on the basis of Delhi Schedule of Rates DSR 2014 printed by C.P.W.D.

(ii)Variations permissible on theoretical quantities.

a) Cement for works with estimated cost put to Tender not more than Rs. 5 Lakhs — 3% plus/minus

For works with estimated cost put to tender More than 5 Lakhs — 2% plus/minus

b) Bitumen for all works — 2.5% plus only & nil on minus side

c) Steel Reinforcement and structural steel Sections for each diameter, section and category — 2% plus/minus

d) All other materials — Nil

RECOVERY RATES FOR QUANTITIES BEYOND PERMISSIBLE VARIATION

S.No.	Description of Item	Rates in figures and words at which recovery shall be made from the contractor	
		Excess beyond permissible variation	Less use beyond the permissible variation
1. 2. 3. 4. 5.	Cement Steel reinforcement Structural Sections Bitumen issued free Bitumen issued at stipulated fixed price		5800/-ton L &T, ACC, Laxshmi Cement, CCI, Birla Uttam or equivalent if applicable

INDIA TRADE PROMOTION ORGANISATION
Engineering Division

No. 180-ITPO/05/Engg/2017-18 **Dated: -** 28/09/2017

TENDER NOTICE

The Senior Manager (Civil), Engineering Division, Room No. 141, India Trade Promotion Organisation, Pragati Maidan, New Delhi on behalf of CMD, ITPO **invites** sealed **Percentage rate** tender for the following work from **approved and eligible contractors of ITPO, CPWD and those of appropriate list of Department of Telecommunications, M.E.S., Railways up to 3.00 PM on 09/10/2017,** which will be opened on the same day by him (or) his authorized representative at **3.30 PM**.

S.No.	Name of work	Time for Completion	Estimated Cost	Earnest Money	Cost of Tender
1	Misc. repairs at toilet blocks at Gate No. 2 & 11 and Railway toilet.	15 days	190413.00	3810.00	590/-
2	**Construction of new single unit toilet for security guards and Mali at ITPO's land at Ghazipur.**	**30 days**	**135644.00**	**2720.00**	**590/-**

Earnest Money should be deposited through Bank Draft drawn in favour of **India Trade Promotion Organisation**, payable at New Delhi (or) cash deposited with the Cashier in Cash Section of ITPO (less than 10,000/-) and Bank Draft/Cash Receipt to be sent with the tender document, while submitting the same.

Conditions and tender forms can be had from the office of the undersigned on production of Registration with the department as mentioned above, PAN Number, **GST Number**, ESI, and EPF Registration Number between **11.00 AM to 3.00 PM** on all working days **up to 06/10/2017** for the tender cost mentioned as above (Non Refundable).

The tender documents are also available on our website www.indiatradefair.com **& www.eprocure.gov.in** and same can be down loaded and used as tender document for submitting the tender. However, the documents required such as two DDs towards Cost of Tender and Earnest money (Demand Draft should be in favour of India Trade Promotion Organisation, payable at New Delhi) should be enclosed in one envelop to be marked **"Cost of tender & Earnest money**ò as well as Registration with the department as mentioned above, PAN Number, **GST Number**, ESI , EPF Registration Number should be enclosed in another second envelope to be marked **"Eligibility Bid**ò . **The Financial bid and schedule of quantities** is to be submitted in separate envelopes marked ñ**Financial Bid** foré é é ò for each work specified in the table above.

These envelopes i.e., ñCost of tender & Earnest Moneyò, ñEligibility Bidò and ñFinancial Bidsò should be put in one envelop, properly sealed and submitted to Senior Manager (Civil), Room No.141

The Financial bids will be opened only of those agencies qualified to tender as per the eligibility criteria. In case the tender is not accompanied with the above and tender does not qualify as per the eligibility criteria, the tender will summarily rejected

(S. K. Gupta)
Senior Manager (civil)

Schedule of Quantities

Name of work: R/M and upkeep ITPO' Premises during 2017-2018.

SH: Construction of new single unit toilet for security guards and Mali at ITPOõs land at Ghazipur.

S. No	Description of item	Qty.	Rate	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
1.1	All kinds of soil.	12.00	166.40	cum	1997.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
2.1	1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	0.50	5390.45	cum	2695.00
2.2	1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size).	1.00	4209.05	cum	4209.00
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
3.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	4.00	4751.65	cum	19007.00
4	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III): 4 graded stone aggregate 12.5mm nominal size)	1.50	263.10	sqm	395.00
5	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.	20.00	47.95	per 50kg cement	959.00
6	Providing & applying a coat of residual petroleum bitumen of grade of VG-10 of approved quality using 1.7kg per square metre on damp proof course after cleaning the surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil.	1.50	91.90	sqm	138.00
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
7.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	3.50	5582.85	cum	19540.00

8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	3.00	125.75	cum	377.00
9	Centering and shuttering including strutting, propping etc. and removal of form for all heights :				
9.1	Suspended floors, roofs, landings, balconies and access platform	5.00	422.30	sqm	2112.00
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
10.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	75.00	56.60	kg	4245.00
11	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	0.50	7390.80	cum	3695.00
12	6 mm cement plaster 1:3 (1 cement : 3 fine sand) finished with a floating coat of neat cement and thick coat of Lime wash on top of walls when dry for bearing of R.C.C. slabs and beams.	2.50	192.85	sqm	482.00
13	6 mm plaster on cement concrete or reinforced cement concrete work with white cement based polymer modified self curing mortar of approved make as per the direction of Engineer-In-Charge.	5.00	146.45	sqm	732.00
14	12 mm cement plaster of mix :				
14.1	1:6 (1 cement: 6 fine sand)	25.00	160.35	sqm	4009.00
15	15 mm cement plaster on the rough side of single or half brick wall of mix :				
15.1	1:6 (1 cement: 6 fine sand)	25.00	185.20	sqm	4630.00
16	6 mm cement plaster of mix :				
16.1	1:3 (1 cement : 3 fine sand)	2.50	143.80	sqm	360.00
17	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	15.00	67.60	kg	1014.00

18	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.				
18.1	Size of Tile 500x500 mm	2.50	988.45	sqm	2471.00
19	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	15.00	744.80	sqm	11172.00
20	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.				
20.1	15 mm nominal outer dia Pipes	15.00	142.95	metre	2144.00
21	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				
21.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1.00	3494.20	each	3494.00
22	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
22.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	1.00	2298.55	each	2299.00

23	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.				
23.1	15 mm nominal bore	1.00	492.55	each	493.00
24	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
24.1	15mm nominal bore	1.00	475.70	each	476.00
25	Providing and fixing PTMT stop cock of approved quality and colour.				
25.1	15 mm nominal bore, 86 mm long, weighing not less than 88 gms	1.00	103.30	each	103.00
26	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design :				
26.1	In 75x75 mm deep chase	18.00	153.00	metre	2754.00
27	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :				
27.1	100 mm diameter	15.00	216.25	metre	3244.00
28	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete.	1.00	187.60	each	188.00
29	Providing and fixing soil, waste and vent pipes :				
29.1	100 mm dia				
29.1.1	Sand cast iron S&S pipe as per IS: 1729	7.00	862.80	metre	6040.00
29.2	75mm dia				
29.2.1	Sand cast iron S&S pipe as per IS: 1729	1.00	712.20	metre	712.00
30	Constructing soak pit 1.20x1.20x1.20 m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	1.00	2116.40	each	2116.00

31	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :				
31.1	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :				
31.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	1.00	8634.10	each	8634.00
32	Painting top of roofs with bitumen of approved quality @ 17kg per 10 sqm impregnated with a coat of coarse sand at 60 cudm per 10 sqm, including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete :				
32.1	With residual type petroleum bitumen of grade VG -10	10.00	102.50	sqm	1025.00
33	10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat:				
33.1	With common burnt clay F.P.S.(non modular) brick tile of class designation 10	10.00	596.70	sqm	5967.00
34	Providing and fixing 100 mm diameter and 60 cm long rain water spout in cement mortar 1:4 (1 cement : 4 fine sand).				
34.1	Stone ware spout	1.00	90.85	each	91.00
35	Finishing walls with water proofing cement paint of required shade :				
35.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	30.00	58.80	sqm	1764.00
36	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				

36.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	10.00	112.30	sqm	1123.00
37	Providing and fixing uplasticised PVC connection pipe with brass unions :				
37.1	45 cm length				
37.1.1	15 mm nominal bore	4.00	67.80	each	271.00
38	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :				
38.1	Rectangular shape 453x357 mm	0.50	752.80	sqm	376.00
39	Providing and fixing CPVC Union in CPVC. pipe including cutting and threading the pipe and making long screws etc. complete (Newwork) :				
39.1	15 mm nominal bore	4.00	206.75	each	827.00
40	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	1000.00	7.20	sqm	7200.00
41	Neat cement punning.	1.50	42.60	sqm	64.00
		Total			135644.00

Note:-

1. The rates should be quoted exclusive of GST as applicable
2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment.
3. Contractual Labour Act Registration if applicable

M(C) SM (C)

INDIA TRADE PROMOTION ORGANISATION
(Engineering Division)

CORRIGENDUM TO FORM 7/8/9 (CPWD) MUST BE READ ALONGWITH THE PAMPHLET

S.No.	FOR	READ
1.	Government of India	India Trade Promotion Organisation
2.	C.P.W.D. or Government	India Trade Promotion Organisation
3.	CPWD -7/8/9	CPWD 7/8/9
4.	President/President of India	C.M.D ITPO
5.	Chief-Engineer	General Manager (Works)
6.	Superintending Engineer	Dy. General Manager (Civil)/SM (Civil)
7.	Engineer-in-charge/Divisional Engineer/Executive Engineer/Divisional Office	**Senior Manager (Civil)**
8.	Sub-Divisional Officer/Asstt. Engineer	Deputy Manager (Civil)
9.	Administration Head	C.M.D. /General Manager
10.	Ministry of Works & Housing	ITPO /Ministry of Commerce
11.	CPWD Code, Paragraphõ90	Shall be applicable t o ITPO works
12.	DSRõ2014	Shall be applicable to ITPO works
13.	CPWD specifications 2009 part ï I & II	Shall be applicable to ITPO works
14.	DSR (Internal) 2014 for Electrical works	Shall be applicable to ITPO works
15.	CPWD specifications (Internal) 2005 for Electrical works	Shall be applicable to ITPO works
16.	DSR External 2014 for Electrical works and specifications	Shall be applicable to ITPO works
17.	Provision of Section 12 Sub-Section (i) of the works man compensation	Shall be applicable to ITPO works
18.	CPWD safety Code framed from time to time	Shall be applicable to ITPO works
19.	CPWD maternity benefits to labour	Shall be applicable to ITPO works
20.	Model Rules of the protection of health and sanitary appointment for workers employed by CPWD	Shall be applicable to ITPO works
21.	CPWD contractor labour Regulations	Shall be applicable to ITPO works

MANAGER (CIVIL) **Senior Manager (Civil)**

ADDITIONAL CONDITIONS

1. The work shall be carried out strictly as per CPWD specifications 2009, Part I & II with upto date correction slips.
2. The contractor shall take approval from the Manager (Civil)/Electrical in writing for collection and stacking of materials.
3. The contractor must follow CPWD Safety Code as provided in general conditions of contract for CPWD Works.
4. Any damage done by the contractor or his workmen to any existing work during the course of execution of the work shall be made good by him at his own cost.
5. Contractor shall clear the site thoroughly of all rubbish etc. left out of his materials immediately on completion of the work and properly clean the site around the building to the satisfaction of the Engg.-in-Charge. Otherwise the site will be cleared by the department at his risk & cost to remove and clean the site.
6. The contractor to whom the work is awarded will have to sign the agreement on non judicial stamp papers of Rs.50/- and the cost of such stamp paper will be borne by the contractor.
7. Cement bags shall be stacked by the contractor at space provided by ITPO of stipulated quantities at his own cost in his own.
8. Cement shall be kept under double lock system in space provided by ITPO fixed with the door. The key of the lock shall remain with representatives of the Engg-in-charge at the site of work and that of other with the contractor or his authorized agent. Day to day issue shall be entered in the prescribed register and signed by the contractor or his authorized agent.
9. All incidental charges of any kind whatsoever including cartage, cutting and wastage etc. shall be borne exclusively by the contractor and nothing extra will be paid to him on this account.
10. **The contractors are required to submit the bill on their printed letter head having detail of GST Number for release of payment**.

MANAGER (Civil) **Senior Manager (Civil)**

India Trade Promotion Organisation
(Engineering Division)

Categories of Employees — All inclusive Minimum Rates of Wages per day

A. Un-Skilled

1	Mazdoor	Rs. 513.00	Each Per day
2	Mazdoor Coolies	Rs. 513.00	Each Per day
3	Helper to Mason, Fitter Carpenter & Painter	Rs. 513.00	Each per day
4	Any other categories doing un-skilled work	Rs. 513.00	Each per day

B. Semi Skilled

1`	Sewer man	Rs.565.00	Each Per day
2	Chowkidar	Rs.565.00	Each per day

C. Skilled

1.	Glazier	Rs. 622.00	Each per day
2	Carpenter	Rs. 622.00	Each per day
3	Sanitary Fitter	Rs. 622.00	Each Per day
4	Spray men for Road	Rs. 622.00	Each per day
5	Mason	Rs. 622.00	Each per day
6	Black Smith	Rs. 622.00	Each per day

M (Civil)
ITPO

Senior Manager (Civil)
ITPO

AGREEMENT

AN AGREEMENT is made thisé é é é é é é é é é é é é é é é é é BETWEEN the India Trade Promotion Organisation. A company Incorporated under the companies Act, 1956 and with its registered office at Pragati Maidan New Delhi-110 001, which expression shall include its successor, unless repugnant to or Excluded by the contract here of and assignees of and represented by its Managing Director, ITPO the first party (hereinafter called the Authority) and by its sole proprietor/partners, Managing Director é .(which expression shall be including his/its successorŝs heirs, executors, representative and or assignees of the second party (hereinafter called the contractor).

WHEREAS the Authority has, under Notification No. é ...é ..

WHEREAS the contractor has submitted tender for carrying out the work as above as per the tender document page to and has represented that in conformity with his/its obligation contained in the tender as modified by the correction slips and corrigendum contained he/it shall carryout the same truly, faithfully and honestly.

THE SAME has been accepted by both the parties on the terms and conditions, corrections, corrigendum contained in the tender as modified as well as the letter of acceptance Issued party No. 1 annexed here to as.

The same shall be binding on both the parties.

IN WITNESS WHEREOF, the parties have signed the deed of agreement on the date, month and year referred to above.

At New Delhi.
WITNESS

1. ________________________________ Party No. 1

2. ________________________________ Party No. 2