

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Senior Manager

Name of Work : Setting up of stalls for India International Leather Fair-2023,2024 & other events at Chennai.(2 years)

Sub-Head:

Construction of stalls with pre fab Octonorm System, providing Carpet, Furniture items, conservancy etc. (On hire basis for fair period)

Contract No:178-ITPO/ROC/C-E/2022-23/109 dated: - 22.12.2022

Bidder Name :						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) NOTE:- 1.The rates should be quoted exclusive of GST as applicable 2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment. 3. Contractural Labour Act Registration if applicable.						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Construction of booth with spotless superior quality pre-fab aluminum O.C. system bright finished powder coated at site of work with Polychem panels and fascia of approved colour and shade i/c fascia writing with poly vinyl superior quality self sticking cut out letter up to 4” height, Providing office cabin where ever required i/c attending addition/alteration and maintenance during the fair period and dismantling the same after close of the fair ,cleaning the site i/c vinyl digitally printed fascia on the under lay of polychem/sun board/laminated panel of reqd. size & as per Drawing attached etc. complete and as per the direction of Engineer-in-charge. (on hire basis for duration of fair) a) Having logo & extension i/c numbering as per drawing enclosed. Drawing-A	9100	Sqm	162.80	1481480.00	INR Fourteen Lakh Eighty One Thousand Four Hundred & Eighty Only
1.1	b) Extra for using Maxima System for front vertical and Facia members instead of O/c system as per Drawing-B Note:- Qty. payable as per item no. 1	9100	Sqm	46.25	420875.00	INR Four Lakh Twenty Thousand Eight Hundred & Seventy Five Only
2	Providing Registration counter made with superior quality O.C. system including lockable door, fascia write up, colored vinyl on panels, glass panes, and counter of size (length as per front opening of booth x 0.50 m width x 0.75 m height) i/c scratch less laminated top with projected shelf in front of counter and queue manager etc as per drawing and as per the direction of Engineer-in-Charge. (The item includes, Octonorm system, lockable door, counters, front shelf and fascia write up colored vinyl on panels, glass panes, queue manager etc complete all. (On hire bases). a) As per drawing R-1 but without roof	135	Sqm	453.25	61189.00	INR Sixty One Thousand One Hundred & Eighty Nine Only
2.1	b) As per drawing R-1 with roof i/c covering roof with G. I. sheet/Profile sheets/Canopy structure with water proof Fabric/ Waterproof cloth.	20	Sqm	488.40	9768.00	INR Nine Thousand Seven Hundred & Sixty Eight Only

3	Providing & Laying new needle punch non- woven carpet of genuine fiber minimum overall weight 1000gm/Sqm(+/-5%) having minimum 3.90 mm thickness preferable containing 375 gm polyester fiber or equivalent fiber (+/-5%) and the carpet should not loss the thickness more than 25% after 1000 impact & of required shade in passages including pasting with solution/double side tape at ends wherever required including covering with polythene sheet till the opening of the fair (on hire basis)	30000	Each	65.12	1953600.00	INR Nineteen Lakh Fifty Three Thousand Six Hundred Only
4	Hiring of table/counters in round/rectangular shape as required with laminated top of size 1.00 m x 0.50 m x 0.75 m rectangular or 1.00 m, dia in pretty good condition and as approved by Architect/Engineer-In-Charge. (on hire basis) a) Without lock	870	Each	101.75	88523.00	INR Eighty Eight Thousand Five Hundred & Twenty Three Only
4.1	b) Lockable	10	Each	122.10	1221.00	INR One Thousand Two Hundred & Twenty One Only
5	Hiring of good quality chair in attractive colours with nickel polished/powder coated frame & cushion seat & back as per the direction of Engineer In charge. A) Stationary type. (on hire basis)	2600	Each	81.40	211640.00	INR Two Lakh Eleven Thousand Six Hundred & Forty Only
6	Providing built up podium of size 1 Mx1M with pre-fab system with height as under (on hire basis) a) 400 mm height	15	Each	20.35	305.00	INR Three Hundred & Five Only
6.1	b) above 400 mm height	15	Each	20.35	305.00	INR Three Hundred & Five Only
7	Hiring of plastic waste paper basket of medium size for full duration of the fair and as per the direction of Engineer-in-Charge. (on hire basis)	700	Each	4.07	2849.00	INR Two Thousand Eight Hundred & Forty Nine Only
8	Providing & fixing computerized cut PVC/vinyl self-sticking letters of 3'' to 4'' height on fascia as per the direction of Engineer-in-Charge (on hire basis)	25	Each	4.07	102.00	INR One Hundred & Two Only
9	Providing & fixing shelves of size 1.00 m x 0.30 m / hanging rod one meter long with sufficient "S" hooks connected to O.C. System with brackets to take sufficient load with:- a) 5 mm thick glass panes or one meter hanging rod with sufficient 'S' hooks. (on hire basis).	1950	Each	122.10	238095.00	INR Two Lakh Thirty Eight Thousand & Ninety Five Only
10	Hire charges for providing and fixing Octonorm pre-fab aluminum system ply panels of required size in pretty good condition and as per the direction of Engineer-in-charge. (on hire basis) (a) Full ply Panels	360	Each	122.10	43956.00	INR Forty Three Thousand Nine Hundred & Fifty Six Only
10.1	(b) Half ply panels / fabric panels (fabric to be supplied by ITPO)	110	Each	40.70	4477.00	INR Four Thousand Four Hundred & Seventy Seven Only
10.2	(c) 4mm thick Half Glass Panels	5	Each	244.20	1221.00	INR One Thousand Two Hundred & Twenty One Only
11	Hire charges for providing and fixing the octonorm system door in pretty good condition with locking arrangement etc complete and the direction of Engineer In charge.(on hire basis)	2	Each	610.50	1221.00	INR One Thousand Two Hundred & Twenty One Only
12	P/F wooden ramp made up of 19 mm thick commercial board of overall width o.60m & 3.00mtr length to cover the electrical cables crossing through passages during fairs etc. complete & as per the direction of Engineer-in-charge.(on hire basis)	10	metre	122.10	1221.00	INR One Thousand Two Hundred & Twenty One Only

13	Providing Pagoda structure made up of Aluminum Structure covered with water proofing and fire retardant sheet like Shri Ram Fabric & should be strong to sustain the high speed wind pressure, centre height 10 feet to 12 feet with span of from 5 or 6 m. All three covered with SRF sheet & placing of queue manager wherever required as per the direction of Engg.-in-charge including wooden flooring as per site requirement. (on hire basis for duration of fair)	270	Sqm	305.25	82418.00	INR Eighty Two Thousand Four Hundred & Eighteen Only
14	Information/form filling counter made with superior quality O.C. system, with fascia at the height of 2.40m, and the size of the counter will be 1.00m x 1.00 m x 1.00 m with scratch less laminated top as per the direction of Engineer-in-Charge. (The item includes octonorm system wall, fascia and counter etc complete).(on hire basis) (a) 1 m long	40	Each	610.50	24420.00	INR Twenty Four Thousand Four Hundred & Twenty Only
15	Arrangement for upkeep of entire Halls i/c passage, shell & bare booths/stalls, entire inauguration function site, registration counters etc. in neat and clean positions for complete tenancy period (construction period, fair period & dismantled period) i/c placing of sufficient number of big size dust bins at different places. The payment shall be made to consider 9 Sqm of area per booth for all shell & bare scheme area booths.	2600	Each	81.40	211640.00	INR Two Lakh Eleven Thousand Six Hundred & Forty Only
16	Hire charges for providing and installation of arm type spot light fitting (powder coated) with 100 watt comptalux lamp (pin/screw type) suitable for mounting on Octonorm system with rail and plug type accessories complete with connection, interconnection sub main circuit control wiring & switch gear etc i/c their maintenance during fair period etc. as required	6500	Each	81.40	529100.00	INR Five Lakh Twenty Nine Thousand One Hundred Only
17	Hire charges for installation testing & commissioning of 5/15 A 6 pin switch socket universal combination gang box type complete with earthing the third pin with suitable size of copper wire to be provided in various stands/stall complete with connection interconnection sub main & circuit wiring etc controlled with suitable capacity switchgear etc. i/c their maintenance during the fair period.	1000	Each	61.05	61050.00	INR Sixty One Thousand & Fifty Only
Total in Figures					5430676.00	INR Fifty Four Lakh Thirty Thousand Six Hundred & Seventy Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				