

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: Sr. Manager (ADD)

Name of Work : Construction of hanger for AAHAR'25 Exhibitions at Bharat Mandapam, New Delhi (all on hire basis).

Contract No:

Bidder Name :						
<b>PRICE SCHEDULE</b> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only ) <b>NOTE:-</b> 1.The rates should be quoted exclusive of GST as applicable 2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment. 3. Contractural Labour Act Registration if applicable.						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1.00	Providing International Hangers Hard Pressed extruded aluminum structure make of Roder / Loser berger or IIT certified Indian hanger of Fab India/ G.S Oberoi or equivalent in the form similar to air craft hanger covered with high gloss PVC flame retardant sheet according to DIN 4102 B-1, M-2, BS 5438/7837: USA NFPA 701 or equivalent with hot dripped galvanized steel connections to DIN 50976 or equivalent and applied weight should be strong to sustain the high speed wind pressure, centre height 20 feet to 40 feet with various span from 20M to 50M. as per requirement with a provision of front and back covered with same material complete with aluminum glass entry & exit doors of size 5.00M wide or above and sufficient numbers including general lighting as per the direction of Engg.-in-charge (on hire basis for duration of fair) and the cost of cloth false ceiling will be paid extra with Aluminum Structure. a) Span of 10Mtr to 50 Mtr	6850.00	sqm		0.00	INR Zero Only
2.00	Providing false wooden flooring of 4" to 6" ht or as per site requirement from ground level and made with 19mm thick hard board and bed supported with providing 2"x2" wooden battens in properly leveled having no undulation, create no sound on using and joints should be in required level complete as per the direction of Engg-in-charge (on hire basis for duration of fair). a) Using good condition used board on top of floor.	8300.00	sqm		0.00	INR Zero Only

3.00	P/F 12 mm commercial ply wood of approved make preferably ISI make with nails/screws on existing wooden platform of hanger etc. complete and as per direction of Engineer In charge (On hire basis)	8300.00	each		0.00	INR Zero Only
4.00	Covering the side walls around the hangers at various places at Pragati Maidan with bamboos & white cloth Fabric stitching and fixing properly as per the direction of Engineer-in charge. ( All on hire basis)	10500.00	each		0.00	INR Zero Only
5.00	Hire charges of JCB Machine with operator for excavation, removing the tree routes etc including the leveling the surface for erection of hanger etc complete as per the direction of engineer-in charge	16.00	each		0.00	INR Zero Only
6.00	Hire charges for providing air-conditioning facility in various hangers at different locations in Bharat Mandapam complex during the event by using air-cooled package/Chiller unit/split air-conditioning units of suitable capacity ,fire retardant fabric ducts and electrical connection from nearest source of power up to 30mtrs along with connecting refrigerant piping from outdoor to indoor units, gas charging, internal electrical connections complete with installations testing & commissioning of the units in all respects and maintenance of the equipments during the event.	6850.00	sqm		0.00	INR Zero Only
7.00	Hire charges for providing electrical power connections of various connected rating with suitable size of aluminum/copper 3 ½ /4 core armoured cables and earth wire controlled with suitable capacity switch gear i/c end termination laying of cable on floor/trench/carpet and tapping with power supply from permanent DB of CPWD /ITPO in various hangers/halls i/c connection inter connection and maintenance during the event. (the cables & other wiring needs to be put under the wooden ramp/rubber covering mat etc as required as per the direction of engineer in charge).	1000.00	each		0.00	INR Zero Only
8.00	Hire charges for providing, installation, testing and commissioning of 60-80 watt LED fitting mps to be mounted on wall/board/trees/existing street light poles etc. complete with connection, interconnections, sub main and copper circuit wiring and with suitable capacity switch gear etc. including their maintenance during the fair period at various exhibition.	100.00	each		0.00	INR Zero Only
<b>Total in Figures</b>					<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>				

**Note: GST will be charge extra as applicable**