

Item Rate BoQ

Tender Inviting Authority: India Trade Promotion Organisation, Bharat Mandapam, New Delhi

Name of Work: Provision of Sound & Display System in Plenary Hall, Convention Center at Bharat Mandapam, New Delhi; Supply, Installation, Testing and Commissioning of Projection System having Projector, Projector Screen and Supporting Backend Equipment, Integration with existing system in Plenary Hall, Convention Center at Bharat Mandapam, New Delhi

Contract No:

Name of the Bidder/Bidding Firm / Company	
---	--

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE incl. GST@18% and all Taxes and duties in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT incl. GST@18% and all Taxes and duties		TOTAL AMOUNT in Words
1	2	4	5	13	53	0.00	NR Zero Only
1	Supply, Installation, Testing and Commissioning of Projector 3-chip DLP, should have 3 laser diodes for true color production(Red,green,blue), Min output resolution 3840 x 2160 (LHD 4K), brightness min 25,000 lumens, RGB Laser 1 DLP digital projector, Contrast Ratio : min 2000:1, lamp life minimum 40000 hours, Cine directional lens/horizontal and vertical lens offset, frame rate should be 60Hz or better, inputs: SDI, HDMI or more, Controls: Ethernet (10/100) or more, Noise should not be more than 55dB, type of lens zoom, lens throw ratio should be 4:1, 0.1 or better, typical power consumption should not be more than 300W, operating temperature 10-35 C or better, complete with standard accessories and like as required as having Defect Liability period of 3 years per direction of engineer in charge. Make: Barco/Christie/NEC	2,000	Nos				
2	Supply, Installation, Testing & commissioning of a Motorized top tensioned ceiling mount projector screen having viewing area of 7.7M x 4.4M or better, 16:9 aspect ratio, with black borders at all sides or better, thickness of 0.70mm or 0.02mm or better, Projector basic fabric or better, Seamless fibre glass fabric, Seamless metal octagonal casing with one powder coated front White/black options, heavy duty branded tubular motor/heavy bottom Rod to make screen flat and straight, low voltage controller to make third party automation or bigger, RF remote control up to 8 meter or better, in line switch for fabric: flip and retract as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Delta/Prime/Chaper	2,000	Nos			0.00	NR Zero Only
3	Supplying, Installation, Testing and Commissioning of fixed hanging arrangement for Motorized projector screen using suitable gauge rope wire minimum 4 numbers as per load capacity of the screen and required metal rod duly welded from main truss to fix the rope wire with all accessories, welding and metal work as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Custom	2,000	Nos			0.00	NR Zero Only
4	Supplying, Installation, Testing and Commissioning of fixed hanging arrangement for Projector using suitable gauge thread rod and metal plate to mount the projector as per the load of the projector with all the accessories, welding and metal work as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Custom	2,000	Nos			0.00	NR Zero Only
5	Supply, Installation, Testing & Commissioning of Video Transmitter having HDMI input and, Twisted Pair output with scaling, 1 distributes full 4Kx4.4 Video end-to-end securely as well as audio, control, Ethernet, 100 meter or better distance support, Should have HDCP 2 compliance or better, Should have RS-232 & IR control port 5 or more, should support ESD, having stereo audio input, complete with standard accessories as required having Defect Liability period of 3 years as per tender specifications. Make: Ighwaer/AMV/Edison	2,000	Nos			0.00	NR Zero Only
6	Supply, Installation, Testing & Commissioning of Receiver having Twisted Pair input and HDMI output with scaling, it distributes full 4Kx4.4 Video end-to-end securely as well as audio, control, Ethernet, 100M (200) or better distance support, Should have HDCP 2 compliance or better, Should have RS-232 & TCP/IP PORT RJ45 connectors or more, should support ESD, having stereo audio output, complete with standard accessories as required having Defect Liability period of 3 years as per tender specifications. Make: Ighwaer/AMV/Edison	2,000	Nos			0.00	NR Zero Only
7	Supply, Installation testing & commissioning of Matrix Switcher having 4 or better HDMI input, 4 or better HDMI output, Supports signal resolutions up to 4K at 60Hz with 4:4:4 color sampling, HDCP 2.2 compliant or better, should support ESD, Audio de-embedding, TCP/IP, RJ45, RS-232 & USB control port, complete with all standard accessories as required having Defect Liability period of 3 years as per tender specifications. Make: Ighwaer/AMV/Edison	1,000	Nos			0.00	NR Zero Only
8	Supply, Installation, testing & commissioning of 1.0 mtr or more Standard HDMI (M) to HDMI (M) Cable as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Extron/Berly AV/Bedden	5,000	Nos			0.00	NR Zero Only
9	Supply, Installation, testing & commissioning of 4 pairs 23 AWG solid, twisted and shielded cable, Conductor made up of: Solid annealed bare copper conductors or better complete with standard accessories as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Extron/Berly AV/Bedden	305,000	Mtr			0.00	NR Zero Only
10	Supply, Installation, Testing & commissioning of 4 pairs 24 AWG solid, twisted, and shielded cable, Conductor: Solid annealed bare copper conductors or better, complete with standard accessories as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Extron/Berly AV/Bedden	305,000	Mtr			0.00	NR Zero Only
11	Supply, Installation, testing & commissioning of 3 core 2.5sqmm Power cable for projector screen and projector, complete with standard accessories as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Polyabarequivalent	300,000	Mtr			0.00	NR Zero Only
12	Supply, Installation, testing & commissioning of Connectors & accessories as required having Defect Liability period of 3 years as per direction of engineer in charge. Make: Neutrik/Equivalent	1,000	Lot			0.00	NR Zero Only
13	Supplying and drawing 3" 45sq mm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/PVC conduit as required.	106,000	Mtr			0.00	NR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	NR Zero Only
<b>Quoted Rate in Words</b>							<b>INR Zero Only</b>