Tender Inviting Authority: SM(Moin)

Name of Work:- R/M & upkeep of ITPO premises during 2024-25

SH:- Providing service of 12 HP diesel pump sets and running Tractor PTO driven positive displacement rotary lobe pump on various locations at Pragati Maidan new delhi.

## Contract No:

Bidder Name :

## PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this to Bidder Name and Values only)

## NOTE:-

- 1. The rates should be quoted inclusive of GST as applicable
- 2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. I
- 3. Contractural Labour Act Registration if applicable.

NUMBE	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #
Sl.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT
No.					
1	2	4	5	6	54
1.01	Hiring of 12 HP trolly mounted diesel engine pump set with operating staff round the clock with 100x100mm suction & delivery along with 100mm dia. P.V.C pipe 25 m long, foot valves complete for removal of water logging from different locations as and when required by Engineer-in –charge including cost of all accessories, operator, tubricant oil, caution board / sign board, barricading, watch & ward, tents / shed etc. The unit rate is for one pump per day (day means 24 hours of a day). Note:- 1. Contractor shall provide smart phone to concerned operator and supervisors and share their numbers to the department on their letter heads. The contractor will ensure that such mobile numbers remain all the time active till completion of work. Nothing extra shall be paid on this account.  (A) Idle Period				
		225.00	Day	3843.100	864698.00
1.02	(B) Running Period	540.00	Hour	223.77	120836.00
2.01	Providing & running tractor PTO driven positive displacement Rotary Lobe Pump of capacity 250-300 cum/hour, 100/150 mm dia suction pipe & delivery pipe having length upto 300m. Tractor Idiling speed 540 rpm scalable to 600 rpm round the clockat site of work for pumping balling out drainage/storm water sump, drain, road surface, emeergency dewatering etc. including all incidental charges as and when required including carriage of pump,, engagging operator, chowkidar and necessary T & P as required for smooth running of pump complete as per direction of Engineer in charge  (A) Idle Period				
		300.00	Day	5469.00	1640700.00
2.02	(B) Running Period				40004.00
	Note: The rates should be quoted inclusive of GST as applicable	1150.00	Hour	373.74	429801.00
3.00	Note: The rates should be quoted inclusive of GST as applicable				
Total in Figures		3056035.00			
Quoted Rate in Figures			Select		0.00
Quoted Rate in Words					INR Zero Only

## ender. Bidders are allowed to enter the before payment. TEXT # TOTAL AMOUNT In Words 55 INR Eight Lakh Sixty Four Thousand Six Hundred & Ninety Eight Only INR One Lakh Twenty Thousand Eight Hundred & Thirty Six Only INR Sixteen Lakh Forty Thousand Seven Hundred Only INR Four Lakh Twenty Nine Thousand Eight Hundred & One Only INR Thirty Lakh Fifty Six Thousand &Thirty Five Only INR Zero Only