

Validate Print Help

Percentage BoQ

Tender Inviting Authority: Senior Manager

Name of Work : R/M & upkeep of ITPO premises at Pragati Maidan during 2023-24

Sub-Head: Providing and laying RMC including hiring of JCB at various locations at Pragati Maidan.

Contract No:

Bidder Name :						
<p>PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p> <p>NOTE:- 1.The rates should be quoted inclusive of GST as applicable 2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment. 3. Contractural Labour Act Registration if applicable.</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth and upto floor V level : Concrete of M10 grade with minimum cement content of 220 kg /cum	185	cum	9655.60	1786286.00	INR Seventeen Lakh Eighty Six Thousand Two Hundred & Eighty Six Only
1.1	Concrete of M25 grade with minimum cement content of 300 kg /cum	250	cum	10221.85	2555463.00	INR Twenty Five Lakh Fifty Five Thousand Four Hundred & Sixty Three Only

2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	100	cum	2658.10	265810.00	INR Two Lakh Sixty Five Thousand Eight Hundred & Ten Only
3	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	70	cum	2803.65	196256.00	INR One Lakh Ninety Six Thousand Two Hundred & Fifty Six Only
4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	25	cum	2007.10	50178.00	INR Fifty Thousand One Hundred & Seventy Eight Only
5	Hiring of Hydraulic Excavator, breaker (3D) with driver and fuel etc all complete as per direction of engineer in charge.	400	Per hour	1171.00	468400.00	INR Four Lakh Sixty Eight Thousand Four Hundred Only
6	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	150	cum	219.35	32903.00	INR Thirty Two Thousand Nine Hundred & Three Only
Total in Figures					5355296.00	INR Fifty Three Lakh Fifty Five Thousand Two Hundred & Ninety Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				