

[Validate](#)[Print](#)[Help](#)

Percentage BoQ

Tender Inviting Authority: Senior Manager S.K. Gupta

Name of Work : Resurfacing of road with 40mm thick Bituminous concrete from Gate No. 10 to Hall No. 12, Behind Hall No 12 and near K-6 at Pragati Maidan during 2021-22.

Contract No:

Bidder Name :						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) NOTE:- 1.The rates should be quoted inclusive of GST as applicable 2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment. 3. Contractural Labour Act Registration if applicable.						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On bituminous surface @ 0.50 Kg / sqm	5000	sqm	36.60	183000.00	INR One Lakh Eighty Three Thousand Only
2	Providing and laying Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge. 40/50 mm compacted thickness with bitumen of grade VG-30 @ 5.5% (percentage by weight of total mix) and lime filler @ 3% (percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity.	200	cum	10870.75	2174150.00	INR Twenty One Lakh Seventy Four Thousand One Hundred & Fifty Only

Total in Figures				2357150.00	INR Twenty Three Lakh Fifty Seven Thousand One Hundred & Fifty Only
Quoted Rate in Figures		Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only				