

[Validate](#)[Print](#)[Help](#)

Percentage BoQ

Tender Inviting Authority: Senior Manager S.K. Gupta

Name of Work : Repair to cement concrete pavement and interlocking path along the service road from Gate no 10 to Hall no 7.

Contract No:

Bidder Name :						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) NOTE:- 1.The rates should be quoted inclusive of GST as applicable 2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment. 3. Contractural Labour Act Registration if applicable.						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	650	sqm	108.65	70623.00	INR Seventy Thousand Six Hundred & Twenty Three Only
2	Laying old cement cocrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in- charge. (Old CC paver blocks shall be supplied by the department free of cost).	500	sqm	362.3	181150.00	INR One Lakh Eighty One Thousand One Hundred & Fifty Only
3	Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	300	sqm	951	285300.00	INR Two Lakh Eighty Five Thousand Three Hundred Only

4	Providing and laying in position ready mixed M-25 grade concrete for reinforced cement concrete work, using cement content as per approved design mix, manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work, including pumping of R.M.C. from transit mixer to site of laying , excluding the cost of centering, shuttering finishing and reinforcement, including cost of admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum.Excess/less cement used as per design mix is payable/recoverable separately). All works upto plinth level	14	cum	7997.3	111962.00	INR One Lakh Eleven Thousand Nine Hundred & Sixty Two Only
Total in Figures					649035.00	INR Six Lakh Forty Nine Thousand &Thirty Five Only
Quoted Rate in Figures		Select			0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					