

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Senior Manager (MOINUDDIN)

Name of Work: R/M and Upkeep of ITPO Premises during 2024-25
SH-1 :- Cleaning of drain and sewer line including raising of manhole and drain cover ofg ITPO Old Campus .

Contract No:

Bidder Name :	
---------------	--

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NOTE:-
1.The rates should be quoted inclusive of GST as applicable
2. The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment.
3. Contractural Labour Act Registration if applicable.

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1.00	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm	1350.00	Metre	340.75	460013.00	INR Four Lakh Sixty Thousand &Thirteen Only
2.00	Raising manhole cover and frame slab to required level including dismantling existing slab and making good the damage as required (Raising depth of manhole to be paid separately) :19.26.3 Rectangular manhole 120x90 cm with circular cover 560 mm dia of grade HD - 20	2.00	each	3881.50	7763.00	INR Seven Thousand Seven Hundred & Sixty Three Only
3.00	Circular manhole 140 cm dia with circular cover 600 mm dia of grade EHD - 35	15.00	each	320.15	4802.00	INR Four Thousand Eight Hundred & Two Only

4.00	Cleaning of under ground sump, Over Head R.C.C. Tank (independent staging) including disposal of slit and rubbish, all as per direction of Engineer-in-Charge. The cleaning shall consist following operations:- (i) Tank shall be emptied of water by pumping & bottom shall be cleaned of silt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge.	450.00	sqm	71.30	32085.00	INR Thirty Two Thousand & Eighty Five Only
5.00	Cleaning drain 0.60m wide & 1.20m deep (approx.) at Old Campus & Bhairon Parking, i/c removal of RCC slabs wherever provided, desilting the Mandir sludge & dewatering the effluent water and stacking of malba/waste material & vegetation etc. from drain and finally placing the covers back in its original position etc. all complete as per direction of Engineer-in-charge.	1950.00	Metre	268.44	523458.00	INR Five Lakh Twenty Three Thousand Four Hundred & Fifty Eight Only
6.00	Providing and fixing Precast R.C.C grating with frame size 600 x 600mm horizontal grating including existing grating and making good the damage as required and Make of KK OR Equivalent specification such as load capacity - 20MT, Thickness - 10cm as per IS 12592 Part -I & II all complete as per direction of Engineer-in-charge.	60.00	each	2326.95	139617.00	INR One Lakh Thirty Nine Thousand Six Hundred & Seventeen Only
7.00	Supplying and fixing C.I. cover 300x300 mm with frame for gully trap (standard pattern) the weight of cover to be not less than 4.5 kg	20.00	each	787.00	15740.00	INR Fifteen Thousand Seven Hundred & Forty Only
8.00	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality 19.19.4 EHD - 35 19.19.4.1 Circular shape 560 mm internal dia	25.00	each	2123.80	53095.00	INR Fifty Three Thousand & Ninety Five Only
9.00	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	50.00	cum	263.95	13198.00	INR Thirteen Thousand One Hundred & Ninety Eight Only
Total in Figures					1249771.00	INR Twelve Lakh Forty Nine Thousand Seven Hundred & Seventy One Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				