

Corrigendum for Minutes of Pre bid meeting

Sub: Supply, Installation, Testing and commissioning of New Air Handling units along with related accessories for HVAC Plant for Hall No. 8-10 at Pragati Maidan, New Delhi

Ref. NIT No. 169-ITPO(1)E-E/20-21/2094 dated 08.04.2021 the pre bid meeting held on 13.04.2021 for the above mentioned work and the following agencies attended the same through Video Conference.

- Blue Star Limited
- Edgetech Air Systems Pvt. Ltd.
- Dexter23 Building Solutions
- Manali Engineering India
- Arihant Engg. Pvt. Ltd.

The agencies discussed all the related issues and get clarified on the spot and confirmed the following

Sr. No	NIT PAGE No.	EXISTING PROVISION	May be read as
1	22-23	<p><u>BOQ ITEM NO.1</u></p> <p>Supply Installation Testing and Commissioning of Double skin floor mounted horizontal Air Handling Unit that hasfollowing specifications: Make: ZECO Aircon/EDGETECH/SYSTEMAIR/ABS AIRTECH</p> <p>Static Pressure: Not mentioned</p> <p>.....</p> <p>Special features:</p> <p>.....</p> <p>2. AHUs should be certified for mechanical and thermal performance as per EN 1886(European Standard).....</p>	<p><u>BOQ ITEM NO.1</u></p> <p>Supply Installation Testing and Commissioning of Double skin floor mounted horizontal Air Handling Unit that hasfollowing specifications: Make: ZECO Aircon/EDGETECH/SYSTEMAIR/WAVES AIRCON</p> <p>.....</p> <p>Static Pressure: 65mmWG</p> <p>.....</p> <p>Special features:</p> <p>.....</p> <p>2. AHUs should be certified for mechanical and thermal performance as per EN 1886(European Standard)/AHRI Certified.....</p>
1.01	22-23	13000 CFM -15000 CFM size AHU	15000 CFM size AHU
1.02	22-23	18000 CFM -20000 CFM size AHU	20000 CFM size AHU
1.03	22-23	28000 CFM -30000 CFM size AHU	30000 CFM Size AHU
2	25	<p><u>BOQ Item No. 8.02</u></p> <p>Current Relay, Make: DISTECH/JCI/HONEYWELL/SIEMENS/DWYER</p>	<p><u>BOQ Item No. 8.02</u></p> <p>Current Relay, Make: ABB/SIEMENS/ALSTHOM/UNIVERSAL</p>
3	25	<p><u>BOQ Item No. 9.02</u></p> <p>Temperature Gauge. Make: H.GURU/Equivalent</p>	<p><u>BOQ Item No. 9.02</u></p> <p>Temperature Gauge. Make: H.GURU/FIEBIG/WIKA</p>
4	25	<p><u>BOQ Item No. 9.02</u></p> <p>Pressure-Gauge. Make: SANT/CASTLE/AUDCO/ADVANCE/ZOOTO</p>	<p><u>BOQ Item No. 9.02</u></p> <p>Pressure-Gauge. Make: FIEBIG/H .GURU/JASPIN</p>

- All valves mentioned in the BOQ, pressure rating will be as per CPWD Specification.
- Class of Pipes will be as per CPWD Specification.
- Make of Existing VFD is ABB and repairing of VFD must be done by OEM.
- Electrical connection (internal/external) of AHU, fan motors by providing suitable size of cables and cable trays will be under the scope of work of the agency to make operational the AHU along with complete air conditioning system.
- For any further clarification, the agency may visit the site on any working day between 11:00 AM to 5:00 PM and may contact Manager(E), Shri Raj Kumar Singh (Mob No. 9810917907)

15/04/2021
R. K. SINGH
Manager (E)